SOLARITHM DESIGN & ENGINEERING

PIPE REQUIREMENT SUMMARY

Structure pipe quantity estimate

PROJECT	DATE	STANDARD PIPE LENGTH
Shresth Parisar (E Block)	05 Oct 2026	20 ft

40 x 40 PIPES
74 pcs
With 10-15% extra: 82-86

60 x 40 PIPES
74 pcs
With 10-15% extra: 82-86

80 x 40 PIPES
43 pcs
With 10-15% extra: 48-50

TOTAL PIPES
191 pcs
With 10-15% extra: 211-220

CATEGORY-WISE BREAKDOWN

Quantities in number of pipes

CATEGORY	40 x 40	60 x 40	80 x 40	ROW TOTAL
Purlin	-	43	-	43
Rafter	10	31	-	41
Leg	12	-	28	40
Supports	15	-	-	15
Walkway	25	-	-	25
Bypass	6	-	15	21
Stairs	6	-	-	6
GRAND TOTAL	**74**	**74**	**43**	**191**

IMPORTANT NOTE

PLEASE QUOTE 10-15% EXTRA PIPES OF ALL SIZES FOR ON-SITE VARIATION.

Calculation based on standard pipe length of 20 ft.